

Drillmec HH-300 spec.



ISO 9001
FM 534725



ISO 14001
EMS 567074



ISO 18001
OHS 567075



ICELAND DRILLING



HH-300

Drillmec HH-300

Fast moving trailer mounted automatic drilling rig.

Designed for cold climate and Geothermal applications and is fully capable of working in heavy winds.

Year of construction 2007

It is capable of drilling to 5500 m. with 3 1/2“ DP and to 4000 m. with 5” DP.

Truck loads in transport: 66

Drilling Crew: 1 tool pusher, 1 driller, 1 assistant driller and 2 floor hands per shift plus 1 mechanic with electrical skills.

The overall hydraulic controls of the rig is exceptionally accurate which reduces the wear on the equipment and increases the safety for the crew.



HH-300

Telescopic Mast

Working stroke	16 m
Static Hook load	272 ton
Pull down capacity	30 ton
Clear height	22,55 m
Max casing operation length	14,63 m



HH-300

Substructure

Clear Working height 6,8 m

Front neck 7 axle trailer with double wheel tires designed for CE and Icelandic road rules.

Easy mounting of the rig trailer on the substructure.

This open substructure concept gives an easy access to the BOP's.



HH-300

Top Drive

Drillmec Top Drive driven by hydraulic motors.

The Top Drive can be tilted out from the center well and to the center of the mouse hole for adding or removing a DP.

The benefits of top drives is that if it is necessary to back-ream it is possible to have the circulation on all the time since the top drive is connected to the string.

Another huge advantage for the top drive is that the driller is able to have constant circulation while tripping out reducing the risk of a cuttings slide and differential sticking.

ID full opening	76 mm (3")
Rotation speed	0 to 200 rpm
Torque	5000 daNm
Circulation pressure	350 bar




HH-300

Top Drive

The HH-series rigs are all equipped with an accurate WOB (Weight on Bit) system which is fully automated. The driller sets the WOB and the system keeps it constant. This makes steering in deviated wells much easier and reduces doglegs plus it increases the bits life.

Our experience is that this automatic WOB performs in faster drilling because there is never a lack of load on the bit.



HH-300

Independent Driven Rotary Table

Max. rotation speed 60 rpm

Max torque 1.020daNm

Max opening through the rotary:
698,5 mm (27 1/2")

Max opening through the drill floor without
the rotary 1200mm (47 1/4"). The rotary can
be easily removed.

Automatic power slips

Drill pipe holding cap. 3 1/2" - 5"

Drill collar holding cap. 6 1/2" - 7" - 8" - 11"

Tubing holding cap. 2 3/8" - 2 7/8"

Casing holding cap. 7" - 13 3/8" but larger
casings require manual slips.



HH-300

Automatic hydraulic power tong

Operating diameter is 3,5" - 11"

Max make up torque 18.700 daNm

Max brake out torque 22.500 daNm


Automatic Torque Wrench

The hydraulic torque wrench is mounted on the top drive main body.

Operating diameter is 3 1/8" - 8"

Max make-up torque 8.600 daNm

Max break-out torque 12.300 daNm



HH-300

Automatic hydraulic power tong

Power tong PLC controled fully automatic make up.

Touch screen for make up torque selection.

Less hands involved in making up drill string, less potential injuries.



HH-300

Casing make-up

Running the casing in is an extremely simple task when using the HH-series. The rigs are equipped with a casing make-up tool which clamps on the casing and screws the casing using the top drive. There is a casing backup slips in the rotary table which holds the casing while making-up. The make-up is remotely operated by the driller inside the control cabin.

A big benefit to this casing make-up device allows us to run-in the casing in windy conditions which reduces the risk of stopping operations because of a strong wind.

The HH-series sophisticated hydraulic height, RPM and torque control minimizes damage of the threads.

The use of this equipment eliminates the need for a special service company to run-in the casing.



HH-300

Casing make-up

Casing make-up with double hook, allows the casing to be lifted and rotated with adjustable torque, as well as fluid circulation while running casing. All operated from drillers control cabin.

Casing device



Casing brought up to drill-floor



HH-300


Automatic Pipe Handling System

The HH-300 is equipped with an fast, fully automatic pipe handling system.

The pipe bins are installed by the pipe handler with all the pipes, ready for use.

The pipe handler automatically removes or adds a pipe to the mouse hole according to the workmode (trip-in/trip-out).

Bins storage capacity: 272 DP's total 3700m.



HH-300

Control cabin

The control cabin is ergonomically designed to reduce the strain for the driller and to have all the controls within the drillers reach.

The driller has a full view of the operations on the drill floor and the mast plus a very good view to the mud system.



HH-300

Hydraulic Power-Packs

The rig is powered by two hydraulic power units combined in one silenced container mounted on a trailer. It is possible to run the complete rig with only one unit increasing the rigs running reliability.

One auxiliary hydraulic power unit is mounted on the rigs trailer for rig-up and rig-down purpose and requires only a small generator.



HH-300

Mud system:

Three Drillmec 9T 1000 mud pumps.

Each pump is a triplex single acting 1000 hp pump electrically driven.

Capacity, each pump:

Max volume:

37 l/sec @ 185 bar

32 l/sec @ 215 bar

27 l/sec @ 253 bar

23 l/sec @ 300 bar

19 l/sec @ 350 bar

Max pressure: 350 bar



HH-300

Mud system:

Tank system with mud treatment,
Derrick Flo-line Cleaner 2000, cooling
and mixing unit.

Especially designed for Geothermal
operations.

Tank capacity: 180 m³



HH-300

Power Control Room specially designed for Drillmec HH-300.

The SCR-system is designed to operate:

Four 1470 KVA Generator Sets, CAT 3512B

Three 1000 hp Mud-pumps.

Remotely controlled MCC (Motor Control Center) for the complete rig and mud system.

All the unit is PLC controlled and monitored.





HH-300

Data logging of drilling parameters:

The rig is equipped with a Data Logging and Monitoring system for all major drilling parameters.

All data is stored in a MS-SQL database for easy data access for other systems if needed.

The data is accessible locally using special client software and from the Internet using a standard web browser to monitor the drilling parameters live or to look back at the history of the well.



HH-300

BOP EQUIPMENT

Size - Type - WP – Manufacturer

21 1/4" - Rotating Head - 2000 psi WP - Washington

13 5/8" - Rotating Head - 3000 psi WP - Washington

21 1/4" - Annular BOP - 2000 psi WP - Shaffer

21 1/4 " - Double LWS BOP- 2000 psi WP- Shaffer

13 5/8" - Annular BOP - 3000 psi WP - Shaffer

13 5/8" - Double LXT BOP- 3000 psi WP- Shaffer



HH-300


Accumulator:

R & T unit 1627T.

140 l/m @ 210 bar.

With triplex pump, two air operated pumps and 21 E-series standard bladder 42 liter bottles.

A drillers remote control R & T




Rig Instrumentation:

Automatic recording and monitoring of all major drilling parameters.


All drilling parameters are stored in a MS SQL-database and is accessible on the rig.

This display are also accessible live for our customers, over the Internet using a standard web browser.




ICELAND DRILLING RIG TYR

21 1/4" Stack on 18 5/8" Casing



ICELAND DRILLING RIG TYR

21 1/4" Stack on 13 3/8" Casing



Mud System

Rigs standard mud tank system (See attached drawing)

Please keep in mind that the drawing is only showing 2 shale shakers. The third shaker has been added and can be seen on the overview picture.

TOTAL OF 4 MOBILE UNITS. (Within EU transport regulation). 3 mudtanks and 1 unit with mud hopper and big sack silo. Capacity of standard tank system is 180 M3 with 9 compartments and 1 sandtrap.

Ability to draw from 4 compartmented tanks when mixing (orange pipe in drawing 1). Direct treated mud from the hopper discharge to 7 compartmented tanks. Paddle agitators are in 7 compartments. Sub surface gun lines in 9 compartments.

Tank 1. is the sandtrap. Mud flows from shale shaker into compartment 1. From compartment 1 the mud is picked up by a centrifugal pump (green) that is located in the mud mixing unit and pumped through the Desander and into compartment nr. 2. From there it is picked up by another centrifugal pump (blue) and pumped through the Desilter and into compartment nr. 3.

Mud is then ready to be mixed from compartments 3,4,5 and 6 with new mixed mud from the whopper. The mud is then discharged (orange pipe in drawing 2) from the whopper to compartments 4,5,6,7,8 and 9.


Mud pumps can suck from compartments 4,5,6,7,8 and 9 and from this compartments the mud is pumped into the well.

See further volume of these tanks on the standard mud diagram.

Mud cooler. When using the mud cooler mud is picked up from compartment 3 and from the cooler the mud returns to compartments 3 or 6.

Overview of Drillmec HH-300 Mud system

Picture taken from Rig's mast



TOLLENZANE GENERALI	± 2 mm	TRATTAMENTO TERMICO
CARPIERNA DENSITÀ	± 1 mm	CEMENTAZIONE - TEMPERA
MACHINERY TOLERANCE	± 0.50 mm	BONIFICA VEDI UNN EN 10083/1
QUOTE DESIGNI	± 0.50 mm	TEMPEA INDIVIDUALE
QUOTE CON 2 DECIMALI	± 0.25 mm	HRC
QUOTE CON 3 DECIMALI	± 0.10 mm	durezza superficiale HB
QUOTE CON 4 DECIMALI	± 0.05 mm	corico di servimento N/mm ²
CONCENTRICITÀ	± 0.50 gradi	CONCENTRICITÀ BONIFICA SU: A INDUZIONE: ± 0.50 gradi
ANGOLI		COLLEGAMENTI: ± 0.50 gradi

DR LUMEC DRAULIC TECHNOLOGIES S.p.A.

04/12/2006 CHANGED SHALE SHAKER BY-PASS SYSTEM

04/12/2006 REVISED AS JARBOBANIR INDICATIONS

27/10/2006 22/09/2006

Sanzani M. Sanzani M.

28/09/2006

Sanzani M.

NUMBER CODE: S000 2742

REVISONE: VER. FOGIO SCALA

3-0 1 di 1 1:1


STATO: SORROSSO


GRANITO

SCARICO

STATO: SORROSSO

GRANITO</p





CASING RUNNING USING CASING MAKE UP DEVICE (ATTACHED TO TOPDRIVE) AND AUTOMATIC CASING SLIPS

Install automatic casing slips in table



Casing slips in place.



Soft sling attached to casing



CASING RUNNING USING CASING MAKE UP DEVICE (ATTACHED TO TOPDRIVE) AND AUTOMATIC CASING SLIPS

Controlled lifting of casing up into V door



Lower and attach Elevator to casing



Ensure casing collar comes inside casing make up device




**CASING RUNNING USING CASING MAKE UP DEVICE (ATTACHED TO TOPDRIVE)
AND AUTOMATIC CASING SLIPS**

Lift casing



Lower casing into collar



Rotate casing and make up using top drive make-up



CASING RUNNING USING CASING MAKE UP DEVICE (ATTACHED TO TOPDRIVE) AND AUTOMATIC CASING SLIPS

Lower casing into well and set automatic slips



Release elevator

